

Overview of the Niagara Tunnel Facility Project and Surveying Activities

By Dr. Ahmet Unlutepel, PhD.

1. Introduction

The Niagara Tunnel Facility Project comprises mainly the construction of a 10.4 km diversion tunnel that will divert water from the Niagara River, beneath the City of Niagara Falls, to Ontario Power Generation's (OPG) existing Sir Adam Beck Hydroelectric Power Plant. Other key elements of the project are the construction of an Intake Structure and Channel and an Outlet Structure and Canal.

Currently approximately 1,800 m³ of water per second are available to the Power Plant from the Queenston Chippawa Power Canal and the two existing diversion tunnels. The new tunnel will provide an additional 500 m³ per second for power generation.

The current project began in mid-2004 with pre-qualification of potential contractors and preparation of proposal documents. In 2005, through a competitive international proposal process, OPG awarded Strabag AG with the Design/Build Contract for the new Niagara Tunnel Project. The value of the design/build contract for the Niagara Tunnel Project is approximately \$622 million. Strabag AG, based in Austria, is one of Europe's leading construction companies, with turnover of 10.4 billion Euros per year and a workforce of 53,000. (www.OPG.com).

Strabag has partnered with several Ontario subcontractors for specific construction work on the diversion tunnel, intake and tunnel outlet. Dufferin Construction is the main subcontractor, responsible for the construction of the Intake-Outlet Structure and Canal. McNally International - Marine Division has




Figure 1.1 Project layout (OPG, 2005).

constructed several in-water structures related to the Intake works at the International Niagara Control Works Structure (INCW). Consulting engineers, both local and from abroad include Morrison Hershfield of Toronto for the design of various surface structures and infrastructure engineering and ILF of Austria for the design of the tunnel, Intake and Outlet Structures. OPG has retained Hatch Mott MacDonald, with Hatch Energy, as Owner's Representative, to manage

the project on their behalf.

Construction of the Outlet Canal began in September 2005 and was completed in April 2006. In water works at the Intake site began in April 2006 with in-water drilling and blasting, the construction of two precast block walls and the construction of a cellular cofferdam. The actual boring of the tunnel began September 1st, 2006. Construction is expected to be completed in 2010. (Figure 1.1)

The TBM was launched from the Outlet Canal and will continue to advance until it breaks through into a Grout Tunnel, which will be driven starting from the intake by drill and blast methods. The TBM is currently about 1150 m beyond the outlet portal on its way down with a -7.82 % grade. The TBM is being operated 24 hours a day. Approximately 1.6 million cubic metres of material is being excavated from the tunnel and being transported to the storage site on OPG property by a continuous conveyor. Rowa Tunneling Logistics manufactured a 105 m long backup system consisting of

-Construction layout and deformation monitoring

3.1 Establishment of Control Network

The basic control network is the basis for all surveys carried out both on the surface and in the tunnel including measurements for guiding the TBM, tunnel traverse network measurements, and setting out surveys inside the tunnel.

OPG's surveyors, Monteith and Sutherland Limited, established a basic surface control network by means of GPS and conventional surveying tech-



Figure 2.4.1 TBM is seen at the start position and while disappearing on its route.

4 main units, which carry the equipment required to support the TBM excavation. Rowa provided the essentials for the continuous conveyor belt to remove excavation material, air ventilation, rock bolt-drilling machines, and 360° round shotcreting robots. (Figure 2.4.1)

3. Surveying Tasks for the Tunnel Construction

Surveying applications for the tunnel construction are being executed relative to the established horizontal and vertical control networks. Underground traverse measurements cannot be verified until the tunnel breaks through at the end of the excavation. Hence, measurements for guiding the tunnel excavation are very crucial throughout tunnel construction. Basic surveying tasks for the tunnel construction are as follows:

- Establishment of tunnel control network
- Tunnel control surveys
- Guidance system control

niques in September 2005. As typical with tunneling projects, the surface control network was formed over an area encompassing the entire project area from Intake to Outlet.

The control network consists of four ground monuments at the Intake site area and five at the Outlet site area. The main network for the project area consists of two known horizontal NAD83 UTM 2nd order control points. An additional eight control points were installed around the Outlet area to enter the tunnel with a




Fig. 3.2.1 Tunnel prism bolt and bracket installations on the tunnel wall.



Figure 3.1.1 Pillar type of survey monument at Outlet area.

stronger shaped network that will assist in minimizing breakthrough error. Pillar type installations were used as monumentation to increase the speed and accuracy of the measurement process. (Figure 3.1.1)

3.2 Establishment of Tunnel Control Network

The two fundamental elements of the underground control network, namely 3D control, and elevation control, are being executed accurately with the use of state of the art methods and instrumentation. Generally, the establishment of tunnel control networks is restricted due to the confinement of underground areas. Survey brackets and prism bolts are being installed on the right and left sides of the tunnel walls at approximately 200 m intervals. Additional prism bolts are installed between the bracket sections at a spacing of 100 m. Temporary stations are set up using a tripod, which leads to a better breakthrough accuracy. Figure 3.2.2 shows the arrangement of the survey monuments used in the tunnel.

Benchmarks for leveling surveys inside the tunnel are being installed in

approximately 100 m intervals and precise level measurements are being performed with a Leica DNA 03 digital level and invar rods. Level surveys are being performed back and forth along the tunnel. Tunnel control network point elevations are verified using the level benchmarks.




Figure 3.2.2 Tunnel survey monuments typical section (Unlutepe, 2007).

LEGEND

- A: TBM Guidance Bracket (X,Y,Z)
- B: Traverse Bracket (welded or bolted)
- C: Prism Bolts (X,Y,Z,) (for measurement)
- D: Level bolts (Z)
- E: Temporary Ground Point (X,Y,Z)

3.2.1 Tunnel Control Surveys

The tunnel excavation began from the Outlet Canal, which allowed the transfer of control directly from the surface to underground, thus eliminating the need for shafts, or adits. A control survey closure will be performed at the end of the 10.381 m TBM drive at the Intake area.

Survey control will be transferred into the tunnel in two different ways:

- 1- Survey control is being extended directly through the Outlet Canal into the tunnel.
- 2- Survey control will also be transferred down dewatering shafts at chainage 1+410. Three control points will be established at the top of three shafts and transferred down to the tunnel bottom.

The control network surveys are being performed at approximately 500 m intervals, as the tunnel advances. The surveys are initiated from the surface network in order to check the stability

of tunnel control points. Once the tunnel lining formwork is installed in the tunnel, control surveys may be started from the previously measured tunnel control points. Surveys initiated inside the tunnel will overlap the previous survey to ensure movement has not occurred in the brackets.

The Leica TCA1800 Robotic total station, equipped with ATR and software entitled “Sets of Angles”, make the observing procedure faster and more accurate. Once the underground network measurements are completed, the data is adjusted and the coordinates (E, N, H) of all brackets and prism bolts are updated.

A group of Gyrotheodolite surveys will be performed as a part of the control network surveys during mining prior to breakthrough. The number and location of the surveys to be conducted will be chosen in order to minimize error propagation and achieve the required breakthrough accuracy. A state of the art tunnel surveying software called EUPALINOS of Geodata is being used for the data evaluations and Least Square network adjustments.

Profiling surveys are being performed with the Leica TCA1800 and Leica TCRA 1201 to compare the as-built tunnel surface to the required design surface. The Leica TMS (Tunnel Measurement System) and EUPOLINOS profiling modules are being used for data processing. Profile measurement intervals are chosen to be 3 to 4 m and 30 to 40 points are measured for each section.



Figure 3.3.1 PPS guidance system total station bracket and computer in the TBM control cabin.

Profiling measurements will be repeated to guide the inner lining applications.

3.3 Guidance System Control

The TBM is being guided with Poltinger Precision Systems (PPS) based on the tunnel control network. The PPS guidance system continuously defines the TBM position and compares it with the design tunnel axis. The PPS system receives input measurements from a Leica TCA1800 total station, which is placed on a bracket attached to the left upper wall of the tunnel (Figure 3.3.1). The guidance station bracket is incrementally moved forward as the TBM advances.

Two motor prisms are installed at the predetermined locations on the TBM. The total station measures the position of motor prisms based on the reference station at continuous intervals and sends the data to the PPS computer. A dual axis inclinometer is installed under the TBM main beam to measure the TBM roll and pitch. Design tunnel axis coordinates are entered into the PPS computer in a global coordinate system for the calculations. The PPS system collects all measurement data coming from the total station and inclinometer to the computer placed in the TBM control cabin, and calculates the TBM position and TBM deviation from the design line. These measurements and calculations are being repeated every 10 seconds and the TBM position is updated. The PPS screen in the TBM control cabin displays both the design line and the

horizontal and vertical offsets of the TBM position numerically and graphically. The TBM operator uses the offset information shown on the PPS screen to guide the TBM on the correct path.

The TBM guidance stations are being measured as a part of the tunnel 3D control network to correct for any error that may have accumulated on to the TBM guidance control system.

urement section, 3-D measurements are performed with Leica TCA1800 and TCRA1201 total stations. Settlements are also being monitored using level measurements. Tunnel control network survey monuments are being used for the measurements.

4. Conclusion

The Niagara Tunnel will deliver an additional 500 cubic metres per second

up to date survey methods, instrumentation and software will ensure the successful completion of the project.

References

<http://www.niagarafontier.com/tunnel.html>
http://www.opg.com/power/hydro/new_projects/ntp/index.asp
<http://www.strabag.com>
OPG (May, 2005), Niagara Tunnel Project Brochure, Niagara Falls
Unlutepe A. (May 22, 2007), Surveying Procedures for the Construction of Niagara Facility Tunnel, Strabag INC, Niagara Falls.

Dr. Ahmet Unlutepe is the Survey Manager of Strabag INC at the Niagara Tunnel Project. Dr. Unlutepe has been involved with tunnelling construction in Europe for over 20 years and has worked with the Geodesy Department of Bogazici University in Istanbul researching and teaching for 16 years. He can be reached at ahmet.unlutepe@strabag.ca

Published with permission of OPG.




Figure 3.3.2 PPS guidance system units

3.4 Construction Layout and Deformation Monitoring

In addition to the TBM guidance surveys, other types of surveys performed inside the tunnel include construction layout and deformation monitoring. Construction layout surveys are executed based on the coordinate system of the tunnel control network to guide temporary or permanent works inside the tunnel.

Tunnel convergences are being measured with the Geokon Ealey tape extensometer while the measurement section is within the length of the TBM. Once the TBM leaves the meas-

of water to the Sir Adam Beck Generating Complex. When completed, this additional water will increase generation output from the Beck complex by about 1.6 TWh every year. That's enough electricity to more than meet the needs of a city about twice the size of Niagara Falls. This additional electricity will be clean, and renewable and will benefit both Ontario and the environment.

The use of the most

Sites to See

Greenback Search www.greenbacksearch.com

Saving the environment one search at a time.

“Greenback Search gives back on your behalf. Greenback Search is dedicated to the idea that giving back to the Earth should be simple and easy. We're starting with one of the easiest ideas in the world - using Greenback Search as your search engine. We make it easy to give back when you use Greenback Search by donating 50% of our revenues to organizations that are dedicated to making it easy and affordable to eliminate climate impact and hastening the move to a clean energy future. The benefits of your searches will go to CarbonFund.org.”